HEX HEAD
FASTENERS

FASTEN MEMBRANE
6" O.C. ON BACK
SIDE OF WALL

JM TPO MEMBRANE
ADHERED TO WALL

WOOD NAILER FASTENED
AS REQUIRED

JM TPO MEMBRANE
ADHESIVE

FASTEN 12" O.C. W/
APPROVED FASTENERS

3 COURSING
(OPTIONAL)

JM APPROVED
SUBSTRATE

JM POLYESTER
REINFORCED
BACKER PLY

ASPHALT
PRIMER FOR
MASONRY WALL

FESCANT
PLUS

PRESTO LOCK METAL
COPING COVER

PRESTO LOCK
ANCHOR CLIP

5'-0" MAX. WITHOUT
INTERMEDIATE
VERTICAL FASTENING

FOR WALL FLASHINGS OVER 5'-0"
HIGH INTERMEDIATE FASTENING
IS REQUIRED AT 5'-0" INTERVALS

TPO COATED METAL
REGLET

4" MIN. COUNTER
FLASHING
OVERLAP PAST TOP OF
BASE FLASHING

4" MIN. (1 FLASHING)
OR
6" MIN. (2 FLASHINGS)

1 1/2" MIN. HEAT WELD

METAL COUNTER FLASHING

APPROPRIATE FASTENERS WITH 1"
MIN. Ø PLATE 6" O.C. AT TOP EDGE

CAP SHEET

HOT ASPHALT MBR
FLASHING CEMENT OR
MBR UTILITY CEMENT

CAP SHEET

COVER BOARD

RIGID INSULATION

JM APPROVED DECK

NOTES:
1. REFER TO JOHNS MANVILLE WEBSITE (www.jm.com) FOR MOST UP-TO-DATE INFORMATION.
2. JM POLYESTER REINFORCED BACKER PLY INCLUDES DYNABASE PR OR DYNALASTIC 180 S.
3. ANY CARPENTRY, METAL WORK, OR MASONRY CONSTRUCTION SHOULD BE DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH LOCAL CODE REQUIREMENTS AND/OR PROJECT SPECIFICATIONS. THESE COMPONENTS SHOULD BE REVIEWED AND APPROVED BY A LICENSED DESIGN PROFESSIONAL.
4. INSTALL PRESTO LOCK COPING IN ACCORDANCE WITH INSTALLATION INSTRUCTIONS INCLUDED WITH THE PRODUCT. PREFABRICATED INSIDE/OUTSIDE CORNERS AND END CAPS ARE AVAILABLE TO COMPLETE THE INSTALLATION. SHOP FABRICATED COPINGS SHOULD BE INSTALLED IN ACCORDANCE WITH SMACNA GUIDELINES.
5. VERTICAL JOINTS ARE TO BE OVERLAPPED 4" MINIMUM FOR ALL APPLICATIONS. 3 COURSING WITH MBR UTILITY CEMENT AND FABRIC OR JM MBR FLASHING CEMENT IS RECOMMENDED ON ALL VERTICAL FLASHING LAPS AND INSIDE/OUTSIDE CORNERS EXTENDING PAST LEADING EDGE OF CANT STRIP.
6. PLEASE SEE BITUMINOUS FLASHING SPECIFICATIONS AND THE JM TPO APPLICATION GUIDE FOR A FULL DESCRIPTION OF INSTALLATION INSTRUCTIONS AND REQUIREMENTS WHICH ARE CONSIDERED A PART OF THIS DETAIL.
7. MASONRY SUBSTRATES REQUIRE PRIMING WITH ASPHALT PRIMER PRIOR TO BACKER PLY INSTALLATION. WOOD SUBSTRATES REQUIRE A MECHANICALLY FASTENED BACKER PLY FASTENED 9" O.C. IN BOTH DIRECTIONS.

DRAWING NO.	TPO WALL COVERING WITH BUR BASE FLASHING	
BIT-15 (T) FLASHING WALL	MEMBRANE TYPE: BUR	**JM**
SCALE N.T.S	ISSUE DATE 02-08-19	MAXIMUM GUARANTEE TERM:

Johns Manville